



प्रदेश सरकार
सुदूरपश्चिम प्रदेश
सामाजिक विकास मन्त्रालय
महाकाली अस्पताल
काञ्चनपुर, नेपाल
२०७६

Province Government
Sudurpaschim Province
Ministry Of Social Development
Mahakali Hospital
Mahendranagar, Kanchanpur

Mahakali Hospital, Mahendranagar
Mahendranagar, Kanchanpur
Phone: 50 Bedded Hospital

III Schedule Of Price/Rate

Bill Of Quantity

Descriptions	Quantity	Unit	Rate in Figure	Rate In Words	Amount (NPR)	Remarks
Provisional Sum						
Civil Works						
Clearance in the construction site includes removal of various materials such as shrubs, trees, small boulders, and all as per specifications, drawing and instruction of site engineer.	1.00	LS				
Reinforcement in excavation in foundation including site clearing, timbering, pumping out water from the foundation and disposing the excess soil up to a lead of 10m all complete as per specification, drawing and instruction of site engineer.	1167.00	Cft				
Local Sand Filling Works	4500.00	Cft				
One layer flat brick soling with local chimney brick required sand in flooring and in other required place as per specification, drawing and instruction of site engineer.	5182.00	Sft				
Thick Brick Masonry work in 1:4 cement mortar with first class brick in almost perfect and level including packing the joints and the work in all types of thickness of walls, columns, etc in foundation and ground floor of all complete as per specifications, drawing and instruction of engineer.	659.25	Cft				
C.C. (1:3:6) in floor and foundation using approved quality cement sand and aggregate, including proper slope for draining rain water wash water and finishing by rubbing the floor with sprinkling cement, curing the floor etc. all as per specification, drawing and instruction of site engineer. (Plinth Area	1530.50	Cft				

5.12 based \$10.000

(Signature)
जिहित सिंह राई

जिहित सिंह राई
जिहित सिंह राई